



**ADDENDUM No. 1
April 18, 2024**

TO: ALL PROSPECTIVE BIDDERS

SUBJECT: RFP # PL-04-24-02

Prospective bidders are hereby notified of the following modifications to the above RFP, these modifications shall become a part of the RFP, and all provisions of the RFP, not specifically affected by the Addenda shall remain unchanged.

Proposal Response Form

REMOVE

- Due date 5/3/2024 at 2pm

Scope of work

- Item 4 --- 8" Reinforce Concrete (4000 psi) 8662 SY
- Item 5 --- 6" Compacted Limestone Base (TxDOT 247, Ty"A") 8662 SY
- Item 6 --- 6" Subgrade Treaded with 7% Slurry Lime (by weight) 8662 SY
- Item 7 --- Tensar Triax TX140 Geogrid 8662 SY
- Item 8 --- 6" Concrete Driveway (4000 psi) 211 SY

Project Bid Tabulation Items

- Item 1 --- 8" Reinforce Concrete (4000 psi) 8662 SY
- Item 2 --- 6" Compacted Limestone Base (TxDOT 247, Ty"A") 8662 SY
- Item 3 --- 6" Subgrade Treaded with 7% Slurry Lime (by weight) 8662 SY

- Item 4 --- Tensor Triax TX140 Geogrid 8662 SY
- Item 5 --- 6" Concrete Driveway (4000 psi) 211 SY

Concrete Pavement Joint Plan

Construction Joint

- 1/2" Zip strip, 1/4" Tooled edge both sides w/poly-urethane sealant – self leveling type
- 5" Metal keyway w/ #4 Bar 24" O.C.

ADD

- Due date 5/10/2024 at 2pm

Scope of work

- Item 4 --- 8" Reinforce Concrete (4000 psi) 8662 SF
- Item 5 --- 6" Compacted Limestone Base (TxDOT 247, Ty"A") 962.44 SY
- Item 6 --- 6" Concrete Driveway (4000 psi) 211 SF

Project Bid Tabulation Items

- Item 1 --- 8" Reinforce Concrete (4000 psi) 8662 SF
- Item 2 --- 6" Compacted Limestone Base (TxDOT 247, Ty"A") 962.44 SY
- Item 3 --- 6" Concrete Driveway (4000 psi) 211 SF

Concrete Pavement Joint Plan

Construction Joint

- 3/4" Joint cap, 1/4" Tooled edge both sides w/poly-urethane self leveling type.
- 3/4" Redwood

Specifications for LMWD Parking Lot Reconstruction

Questions or clarifications please contact: Charles Ortiz, District Engineer at (956) 572-0314

END OF ADDENDUM No. 1